

Letter No.: FCID/Est./2025-26/530

Date: 15/09/2025

CORRIGENDUM – 1

With reference to Jharkhand E-Tender for installation of “**CCTV Surveillance Camera and Other Allied Items procurement and installation on SITC basis**” vide tender ID No. – 2025_FCID_104631_1 dated 04/09/2025 the suggestions of all prospective bidder’s after site survey have been discussed and the following changes has been done.

The bidders are advised to take into account the following corrigendum before submission of their bids against this tender.

Sl. No.	Description	As per RFP / BoQ specifications	As per Corrigendum - 1
1.	In RFP Section -III, Check List - B point no. 1	EMD as Bank draft or BG for 60,000/- (Rupees Sixty Thousand only) towards Earnest money deposit.	EMD through online Rs.6,000/- (Rupees Six Thousand only) towards Earnest money deposit.
2.	In BoQ specifications Annexure – 1 point no. – 1	In Annexure – 1 in camera specification point (a) Bullet Cameras – 26 Nos – 2MP IP IR Bullet Camera with Night Vision Resolution: 1080p (1920x1080) Lens: 23.8mm fixed / varifocal IR Distance: 30–40 meters Lens: 23.8mm fixed / varifocal	(a) Bullet Cameras 16 Nos. – 2MP 10 Nos. – 4MP Lens: 2.8mm fixed / varifocal
3.	In BoQ specifications Annexure – 1 point no. – 1	In Annexure – 1 in camera specification point (b) – Dome Camera – 6 Nos.	(b) Dome Camera – 4 Nos.
4.	In BoQ specifications Annexure – 1 point no. – 3 Networking & Accessories	Cabling: Cat6 UTP cable (solid copper, 305m rolls, reputed brand)/ Optical fiber wherever required	Cabling: Cat6 UTP cable (solid copper, 305m rolls, reputed brand)/ Optical fiber is required in outer peripheral wall.
4.	In BoQ specifications Annexure – 1 point no. – 4	1. Surveillance HDD: Minimum 24TB total storage 2. LED Monitor: 40–43”	1. Surveillance HDD: Minimum 12TB total storage. 2. Deleted. 3. UPS: 1 KVA with 30 minutes

		Full HD monitor, HDMI/VGA input 3. UPS: 2-3 KVA Online UPS with 1 hour backup (for NVR, switches & monitor)	backup (for NVR, switches & monitor).
5.	Symbolic Image shown in BoQ Specification.	1. 30 CCTV Surveillance camera installation project on SITC basis	In the image the CCTV camera wiring diagram for installation with DVR to be read as NVR. Also the image shown is a symbolic image to help the bidder for better understating of the project.
6.	Date of submission of Bid	15.09.2025	22.09.2025

All other terms and conditions of the advertisement remain unchanged.

Sd-
Administrative-cum-Accounts Officer

Sd-
Principal